BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO:23**

SCHEDULE-B

NAME OF WORK: Improvements to Footpath & Drains in 16th & 19th cross road & other roads, in Ward no. 13, in SSD

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **RAVIKUMAR B T .**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	171.52	119.17	Rupees One Hundred Nineteen and Seventeen Paise Only
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	63.84	63.3	Rupees Sixty Three and Thirty Paise Only
3	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	35.91	4241.26	Rupees Four Thousand Two Hundred Forty One and Twenty Six Paise Only
4	Removing B.S.Slab of drain and stacking. complete as per specifications.	Sqm	203.49	47.26	Rupees Forty Seven and Twenty Six Paise Only
5	Refixing stone slabs of drains and pointing in CM (1:3). complete as per specifications.	Sqm	203.49	66.05	Rupees Sixty Six and Five Paise Only
6	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications.	Sqm	30.52	323.9	Rupees Three Hundred Twenty Three and Ninety Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	212.8	871.88	Rupees Eight Hundred Seventy One and Eighty Eight Paise Only

B.T. Ravikumar

Signature of the Contractor

Executive Engineer

8	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	212.8	771.05	Rupees Seven Hundred Seventy One and Five Paise Only
9	Providing and laying in position plain cement concrete of mix M 15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	10.64	4507.1	Rupees Four Thousand Five Hundred Seven and Ten Paise Only
10	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	531.18	1537.44	Rupees One Thousand Five Hundred Thirty Seven and Forty Four Paise Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specifications.	Cum	235.36	71.17	Rupees Seventy One and Seventeen Paise Only

B.T. Ramireddy

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,